

C3.1: DESCRIPTION OF THE WORKS

STATUS

In the event of any discrepancy between the Scope of Work and any part of the SABS 1200 Standardized Specifications, the Bill of Quantities or the Drawings, the Scope of Work shall take precedence and prevail in the Contract.

C3.1.1 EMPLOYER'S OBJECTIVE

The employer's objective is to reseal roads in the entire municipal area. This maintenance will increase the useful life of the roads.

C3.1.2 OVERVIEW OF THE WORKS

The employer's objective is to reseal roads in the entire municipal area. This maintenance will increase the useful life of the roads.

C3.1.3 EXTENT OF THE WORKS

The Works to be carried out by the Contractor under this Contract comprise mainly of the following:

- Pothole repair
- includes the furnishing of all materials, plant, labour and equipment
- required sweeping of road surfaces,
- the spraying of herbicide and
- the mixing and spreading of bitumen emulsion slurry on streets and main roads

Construction methods must be such that no property or life is endangered. The employer accepts no responsibility for work that is done outside the site boundaries without the Employers agent's approval.

Sufficient photos of structures, walls and areas that have to be crossed must be taken by the Contractor and handed over to the Employers agent before such operations commence.

The Contractor must program his work in such a way that no construction is to be done during the holiday season and public holidays.

The above description is not necessarily complete and shall not limit the work to be carried out under this Contract.

Approximate quantities of the Works are provided in the Bill of Quantities.

C3.1.4 LOCATION OF THE WORKS

The location of the works will across the entire municipal area.

C3.1.5 TEMPORARY WORKS

No specific temporary works are envisaged in the current design or planned execution of the works except where the Contractor may want to incorporate it as part of his work method. Refer also C3.2.5.