

KOUGA LOCAL MUNICIPALITY - BID No.: 96/2022
HANKEY SANITATION UPGRADE (PHASE 3) :
NEW SEWER PUMP STATIONS IN HANKEY AND CENTERTON

WORK SCOPE PACKAGE 1 : HANKEY SEWER PUMP STATION (CIVIL & STRUCTURAL)

SECTION 11 : WASTEWATER GRINDER (MACERATOR)

ITEM NO	PAYMENT REFERS	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
11	Mech Spec G5.0	<u>SECTION 11 : WASTEWATER GRINDER (MACERATOR)</u> The following Items to be supplied with reference to Drawings 5024-PH3-C102-T and the relevant project specifications.				
11.1.1	G5.1	Supply only, of an in-channel wastewater grinder (macerator) capable to handle flows of up to 50m³/h , and fitted with a Submersible Eletrical Motor (IP68), control panel and configeration, as speffied, to be apporved by the Engineer (to be fully installed within a FRP pre-mould Manhole, measure below).	Sum	1		R 0.00
11.1.2	G5.2	Supply only, of a Fibre Reinforced Plastic (FRP) water tight sewer manhole (1,5m dia, 2,5m deep), as specified, complete with all assecories, grids, guide rails and cover lid.	Sum	1		R 0.00
11.1.2		Erection and installation of complete Macerator plant and equipment supplied under item 11.1.1 & 11.1.2 complete, as per specification of manufacturer.	Sum	1		R 0.00
11.1.3		Commissioning, testing of plant and all equipment under item 11.1.1 & 11.1.2, and issue CoC certification, as per Manufacturers Guidelines and Terms and Conditions.	Sum	1		R 0.00
TOTAL CARRIED FORWARD TO SUMMARY						R 0.00